

ASCE Author Proofs

Important Notice to Authors

Attached is a PDF proof of your forthcoming article in **Journal of Bridge Engineering**. The manuscript ID number is **BEENG-2703**.

No further publication processing will occur until we receive your response to this proof. Please return any corrections within 48 hours of receiving the download email. Your paper will be published in its final form upon receipt of these corrections. You will have no further opportunities to review your proof or to request changes after this stage.

Information and Instructions

- The graphics in your proof have been down-sampled to produce a more manageable file size and generally represent the online presentation. Higher resolution versions will appear in print.
- Proofread your article carefully, as responsibility for detecting errors lies with the author.
- Mark or cite all corrections on your proof copy only.
- Corrections should be sent within 48 hours after receipt of this message.
- If no errors are detected, **you are still required to inform us that the paper is okay** to be published as is.
- You will receive a message confirming receipt of your corrections within 48 hours.

Color Figures

Figures containing color will usually appear in color in the online journal. All figures will be grayscale in the printed journal unless you have agreed to pay the color figure surcharge and the relevant figure caption indicates “(Color)”. For figures that will be in color online but grayscale in print, please ensure that the text and captions do not describe the figures using the colors of the online version.

If you have indicated that you will be printing color figures in color (or choosing Open Access), you will receive an email from ASCE Author Services with a link to the publication fee payment system. Until payment is received, your article will not be published.

Reprints

If you would like to order reprints of your article, please visit <http://www.asce.org/reprints>.

Questions and Comments to Address

The red numbers in the margins correspond to queries listed on the last page of your proof. Please address each of these queries when responding with your proof corrections.

Return your Proof Corrections

- Web: If you accessed this proof online, follow the instructions on the Web page to submit corrections.
- E-mail: Send corrections to ASCE.Production@cenveo.com. Include the manuscript ID **BEENG-2703** in the subject line.

ASCE Open Access

Authors may choose to publish their papers through ASCE Open Access, making the paper freely available to all readers via the ASCE Library website. ASCE Open Access papers will be published under the Creative Commons-Attribution Only (CC-BY) License. The fee for this service is \$1,750, and must be paid prior to publication. If you indicate Yes, you will receive a follow-up message with payment instructions. If you indicate No, your paper will be published in the typical subscribed-access section of the Journal.


Selecting Yes does not commit you to publishing your article as Open Access. You will have the option to cancel the Open Access process later. If you are unsure, we recommend selecting Yes. If you select No now, your paper will be published online shortly after your proof corrections are received, and you will no longer have the ability to publish your article as Open Access.

If you have indicated that you will be choosing Open Access, (or printing color figures in color), you will receive an email from ASCE Author Services with a link to the publication fee payment system. Until payment is received, your article will not be published.


Adding Comments and Notes to Your PDF

To facilitate electronic transmittal of corrections, we encourage authors to use the comments and notes features in Adobe Acrobat or the free Adobe Reader software (see note below regarding acceptable versions). The PDF provided has been “comment-enabled,” which allows you to use the text editing and annotation features.


When you open your PDF in **Adobe Acrobat**, the comments/notes/edit tools are shown on the top tool bars (icons may differ slightly among versions from what is shown below). The important features to know are the following:

Use the **Text Edits** tool ( Text Edits) to insert, replace, or delete text.


- § To **insert text**, place your cursor at a point in the text and select “Insert Text at Cursor” from the text edits menu. Type your additional text in the pop-up box.



- § To **replace text**, highlight the text to be changed, select “Replace Selected text” from the text edit menu, and type the new text in the pop-up box.



- § To **delete text**, highlight the text to be deleted and select “Cross Out Text for Deletion” from the text edits menus (see graphic above).

Use the Sticky Note tool ( Note Tool) to describe changes that need to be made (e.g., changes in bold, italics, or capitalization use; altering or replacing a figure; general

comments) or to answer a question or approve a change that was posed by the editor. Beware that comment bubbles can shift. They are not recommended as a primary text editing tool.


Use the **Callout tool** () to point directly to changes that need to be made. Try to put the callout box in an area of white space so that you do not obscure the text, as in the example below:


Table 1. Behavioral performance in psychophysical pretests

Subject	Target contrast (%)
S1	12
S2	12
S3	15
S4	20
Mean \pm SEM	14.75 \pm 1.89


Each row corresponds to a different subject. Bottom row, mean and SEM across performance for target and mask presented to different eyes; well above chance level.

Please remove fourth line of data

Conducted with the written consent of each subject at the safety guidelines of fMRI research, as approved by the Institutional Review Board of the University of California, San Diego.

§ Use the **Highlight tool** () to indicate font problems, bad breaks, and other textual inconsistencies. You can describe the problem with the Callout tool (above), a sticky note, or by double clicking highlighted text (a pop-up window will appear where you can add your comment).

To access the annotation tools in the free **Adobe Reader** software, select the “view” menu and then “Comment” as shown below. You can also access the text edit tools in Adobe Reader through the “View” menu.



Note: To use the comments/notes features on this PDF you will need Adobe Reader version 10 or higher. This program is freely available and can be downloaded from <http://get.adobe.com/reader/>.

Novel Demountable Shear Connector for Accelerated Disassembly, Repair, or Replacement of Precast Steel-Concrete Composite Bridges

Ahmed S. H. Suwaed¹ and Theodore L. Karavasilis²

Abstract: A novel demountable shear connector for precast steel-concrete composite bridges is presented. The connector uses high-strength steel bolts, which are fastened to the top flange of the steel beam with the aid of a special locking nut configuration that prevents bolts from slipping within their holes. Moreover, the connector promotes accelerated construction and overcomes the typical construction tolerance issues of precast structures. Most importantly, the connector allows bridge disassembly. Therefore, it can address different bridge deterioration scenarios with minimum disturbance to traffic flow including the following: (1) precast deck panels can be rapidly uplifted and replaced; (2) connectors can be rapidly removed and replaced; and (3) steel beams can be replaced, whereas precast decks and shear connectors can be reused. A series of push-out tests are conducted to assess the behavior of the connector and quantify the effect of important parameters. The experimental results show shear resistance, stiffness, and slip capacity significantly higher than those of welded shear studs along with superior stiffness and strength against slab uplift. Identical tests reveal negligible scatter in the shear load-slip displacement behavior. A design equation is proposed to predict the shear resistance with absolute error less than 8%. DOI: 10.1061/(ASCE)BE.1943-5592.0001080. © 2017 American Society of Civil Engineers.

Introduction

During the last two decades, rapid deterioration of bridges has become a major issue due to various reasons including increase in traffic flow; increase in the allowable weight of vehicles compared with those considered in the initial design; harsh environmental conditions; use of deicing salts, especially in countries with cold climates; poor quality of construction materials; and limited maintenance. Many bridges in Europe suffer from the previously mentioned factors (PANTURA 2011), and the same is true for the United States in which one-third of the 607,380 bridges are in need of maintenance (ASCE 2014). Bridge maintenance ensures serviceability along with safety for users and typically involves inspection, repair, strengthening, or replacement of the whole or part of a bridge. Such operations result in direct economic losses (e.g., material and labor costs) as well as indirect socioeconomic losses due to disruption of traffic flow, such as travel delays, longer travel distances, insufficient movement of goods, and business interruption. Depending on the type of bridge and the scale of the maintenance operations, indirect losses might be several times higher than direct losses and constitute one of the major challenges for bridge owners, decision makers, and bridge engineers (PANTURA 2011). Thus, sustainable methods for bridge repair, strengthening, or replacement

that minimize direct costs and traffic flow disturbance are urgently needed.

Bridge decks typically deteriorate faster than other bridge components, e.g., the decks of 33% of the bridges in America are in need of repair or replacement after an average service life of 40 years (ASCE 2014). It is important to note that deck replacement is the typical maintenance decision because repair methods, such as deck overlay, are not sufficient for long extension of the bridge life span (Deng et al. 2016). In the case of steel-concrete composite bridges, removing and replacing their deteriorating deck is a challenging process due to the connection among the deck and the steel beams. Such a connection is traditionally achieved with the aid of shear studs, which are welded on the top flange of the steel beams and are fully embedded within the concrete deck. Therefore, removing the deck involves drilling and crushing the concrete around the shear studs and then breaking the deck into manageable sections (Tadros and Baishya 1998). Such processes are costly and time-consuming and involve the use of hazardous equipment. Other bridge deterioration mechanisms include fatigue or corrosion in the steel beam or in the shear studs. Repair in these cases is again challenging and often questionable in terms of the postrepair structural integrity, whereas replacement of a deteriorating steel beam or shear stud is costly and time-consuming due to the previously mentioned monolithic connection between the steel beam, shear connectors, and concrete deck.

Apart from repairing or strengthening existing bridges, bridge engineers should adopt reparability and easy maintenance as major goals for new bridge design projects. This can be achieved not only by designing bridges based on a lifecycle cost approach that will assess repair costs and losses during their life span but also by changing the paradigm in structural detailing so that bridge structural systems have the inherent potential to be easily repaired, strengthened, or replaced. A possible way to meet this challenging goal is the development and design of novel bridge structural systems that allow bridge disassembly without compromising their structural integrity and efficiency. Rapid bridge disassembly will

¹Ph.D. Candidate, School of Engineering, Univ. of Warwick, CV4 7AL, U.K.; Lecturer, Univ. of Baghdad, Baghdad 10071, Iraq (corresponding author). E-mail: ahmed.suwaed@outlook.com

²Professor of Structures and Structural Mechanics, Faculty of Engineering and the Environment, Univ. of Southampton, Southampton SO17 1BJ, U.K. E-mail: T.Karavasilis@soton.ac.uk

Note. This manuscript was submitted on August 15, 2016; approved on March 8, 2017; published online on [REDACTED]. Discussion period open until [REDACTED]; separate discussions must be submitted for individual papers. This paper is part of the *Journal of Bridge Engineering*, © ASCE, ISSN 1084-0702.

offer the unique advantage of easy replacement of deteriorating structural components; therefore, it will result in the extension of bridge life span with minimum cost and traffic disturbance. In the case of steel-concrete composite bridges, bridge disassembly calls for a demountable shear connector that would allow easy separation of the deck from the steel beam without compromising composite action. The potential for bridge disassembly can be further facilitated by using precast concrete panels that are connected to each other with dry joints, such as those proposed by Hallmark (2012).

Background

Few works developed demountable shear connectors for steel-concrete composite beams. Dallam (1968), Dallam and Harpster (1968), and Marshall et al. (1971) performed tests to investigate the effect of pretensioning on the structural performance of high-strength friction-grip bolts used as shear connectors. A series of tests was conducted on three types of postinstalled bolted shear connectors by Kwon et al. (2010) and showed fatigue strength higher than that of welded studs. Kwon et al. (2011) also tested five full-scale beams using postinstalled bolted shear connectors and showed the effectiveness of such a strengthening strategy for noncomposite bridge girders. Pavlović et al. (2013) investigated the use of bolts as shear connectors and found adequate strength but low initial stiffness, i.e., 50% of that of welded shear studs. Moynihan and Allwood (2014) conducted three composite beam tests using bolts as shear connectors and found performance similar to that of welded shear studs. Dai et al. (2015) performed a series of push-off tests using bolted connectors machined from studs and found a large slip capacity along with shear resistance equal to 84% of that of welded studs at slip displacement equal to 6 mm. Ban et al. (2015), Pathirana et al. (2015), Henderson et al. (2015a), Henderson et al. (2015b), and Pathirana et al. (2016) investigated the behavior of composite beams using blind bolts as shear connectors and found that blind bolts achieve composite action similar to welded studs. Moreover, their research findings imply that blind bolts are beneficial to the time-dependent behavior of composite beams under sustained loads. Liu et al. (2014) investigated the behavior of high-strength friction-grip bolts as shear connectors for composite beams with geopolymer precast concrete slabs and identified three distinct regions in the load-slip behavior along with significant ultimate shear resistance and large slip capacity. Ataei et al. (2016) assessed

the behavior of composite beams using the shear connector proposed by Liu et al. (2014). Their results showed significant initial stiffness due to pretensioning along with ductility higher than that of welded shear studs.

All the previous tests on friction-grip bolts as shear connectors revealed an undesirable large slip displacement due to bolts sliding inside the bolt holes when friction resistance in the steel beam-concrete slab interface was exceeded. It should be noted that the prestandard of Eurocode 4 (BSI 1994) included friction-grip bolts as shear connectors but with major restrictions in the exploitation of their full shear resistance. In particular, the BSI (1994) prestandard allowed the summation of two horizontal shear force resisting mechanisms (i.e., friction in the steel beam-concrete slab interface and shear force resisted by the bolt only) provided that the shear force-slip displacement behavior has been verified by testing. Moreover, Johnson and Buckby (1986) discussed the use of friction-bolts as shear connectors within the framework of the BS5400-5 (BSI 1979) standard for bridges. They mention that the shear resistance of friction-bolts should be assumed equal to friction resistance only, unless all the gaps among the bolt and the precast slabs are grouted after bolt tightening so that bearing of the bolt onto the precast slab will take place immediately after the initiation of slip in the friction interface.

Apart from the bolt sliding issue discussed in the previous paragraph, all the previously proposed bolted shear connectors may not be suitable for precast construction due to different practical reasons. In the case of shear connectors that are pre-embedded in the concrete slab, precast construction tolerances make their alignment with the predrilled bolt holes on the top flange of the steel beam extremely difficult, if not impossible. In the case of shear connectors that are fastened underneath the steel beam after positioning of the precast slab on the top of the steel beam, gaps in the concrete slab-steel flange interface may prevent adequate bolt fastening and cause slab cracking (Biswas 1986). Moreover, working underneath the bridge to fasten the bolts is time-consuming and is generally considered as a substandard unfavorable practice. It is also noted that connectors that are fully embedded within the concrete slab allow uplift and replacement of the slab as a whole but not full disassembly of the composite beam, i.e., replacement of the shear connectors in case of damage due to fatigue or corrosion is not possible.

This paper presents a novel demountable shear connector for precast steel-concrete composite bridges that overcomes all the issues mentioned in the previous two paragraphs. The connector





Fig. 1. Precast steel-concrete composite bridge using the novel shear connector

157 uses high-strength steel bolts, which are fastened to the steel beam
 158 with the aid of a special locking nut configuration that prevents bolts
 159 slipping within their holes. Additional structural details promote
 160 accelerated construction and ensure that the connector overcomes
 161 typical construction tolerance issues of precast structures. The con-
 162 nector allows full bridge disassembly. Therefore, it can address dif-
 163 ferent bridge deterioration scenarios with minimum disturbance to
 164 traffic flow: (1) precast deck panels can be rapidly uplifted and
 165 replaced; (2) connectors can be rapidly removed and replaced;
 166 and (3) steel beams can be easily replaced, whereas precast decks
 167 and shear connectors can be reused. A series of push-out tests are
 168 conducted to assess the behavior of the connector and quantify the
 169 effect of important parameters. The experimental results show shear
 170 resistance, stiffness, and slip capacity higher than those of welded
 171 shear studs along with superior stiffness and strength against slab
 172 uplift. Identical tests reveal negligible scatter in the shear load-slip
 173 displacement behavior. A design equation is proposed to predict the
 174 shear resistance with absolute error less than 8%.

175 **Novel Demountable Shear Connector**

176 The proposed locking nut shear connector (LNSC) is one of the two
 177 demountable shear connectors invented by Suwaed et al. (2016).

- 1.Nut; 2.Washer; 3.Plate washer; 4.Plug; 5.Grout; 6.Slab hole; 7.Bolt;
 8.Conical Nut;9.Conical hole.




F2 : 1 **Fig. 2.** The 3D disassembly and inside view of the shear connector

Fig. 1 shows a steel-concrete composite bridge, which consists of
 precast concrete panels connected to steel beams with the aid of a
 LNSC. The concrete panels have several holes (pockets) to accom-
 modate the shear connectors. Fig. 2 shows a three-dimensional (3D)
 disassembly along with an inside 3D view of the shear connector in
 which all its components are indicated. Moreover, Fig. 3 shows the
 cross section of a steel-concrete composite beam using the shear
 connector. The following paragraphs describe in detail the compo-
 nents of the LNSC and the associated methods of fabrication and
 construction.

The LNSC consists of a pair of high-strength steel bolts (e.g.,
 Grade 8.8 or higher) with a standard diameter (e.g., M16), as shown
 in Fig. 3. These bolts are fastened to the top flange of the beam using
 a double nut configuration, which consists of a standard lower hex-
 agonal nut (Nut 1 in Fig. 3) and an upper conical nut (Nut 2 in Fig.
 3). The upper part of the bolt hole is a countersunk seat with cham-
 fered sides following an angle of 60°, as shown in Fig. 4(c). The
 upper conical nut [Figs. 4(a and b)] is a standard type nut (BSI
 1970) threaded over the bolt and has a geometry that follows the
 same 60° angle so that it can perfectly fit within the countersunk
 seat. The upper conical nut locks within the countersunk seat, pre-
 venting slip of the bolt within the bolt hole. A few millimeters of
 the total height of the upper conical nut appear above the top surface
 of the beam flange (Fig. 3) to resemble the height of the collar of
 welded shear studs (Oehlers 1980). In that way, the LNSC increases
 the contact area of the bolt with the surrounding concrete, which
 delays concrete crushing. Moreover, 5 mm of the internal threading
 of the conical nut is removed, as shown in Fig. 4(b). In that way,
 the bolt is partially hidden inside the conical nut and shear failure
 within its weak threaded length (as seen in other types of bolt shear
 connectors) is prevented. The lower standard hexagonal nut (BSI
 2005c) is used along with a hardened chamfered washer (BSI
 2005d) and a direct tension indicator (DTI) washer (BSI 2009a), as
 shown in Figs. 2 and 3. A proof load [e.g., 88–106 kN for an M16
 bolt, which represents 70% of its ultimate capacity according to BSI
 (2009a)] is applied between the lower nut and the conical nut to
 ensure a robust locking configuration that prevents the bolt from
 slipping within its hole.

The slab pocket is a countersunk hole with an inclination of 5°
 following the recommendations of Vayas and Iliopoulos (2014). A
 typical geometry of a slab pocket, relevant to the test specimens



F3 : 1 **Fig. 3.** Cross section of a steel-concrete composite beam using the shear connector

presented later, is shown in Fig. 5(a). Inside each slab pocket there are two inverted conical precast concrete plugs (Figs. 2 and 3) with geometry following the inclination angle of the slab pocket. A typical geometry of a plug, relevant to the test specimens presented later, is shown in Fig. 5(b). Each plug has a central circular hole with a 26-mm diameter that accommodates an M16 bolt with 10-mm clearance. The diameter of the central circular hole increases from 26 to 40 mm at the base of the plug to accommodate an M16 conical nut with 10-mm clearance, as shown in Fig. 5(b). The dimensions of the plug ensure that shear forces are transmitted from the LNSC to the concrete slab without the risk of premature longitudinal shear failure and/or splitting of the concrete slab. Moreover, the diameters of the plugs are small enough compared with the diameters of the slab pocket to overcome construction tolerance issues typically encountered during precast bridge construction (Hallmark 2012). Grout is used to fill the gaps between the bolt and the hole of the plug as well as the gaps between the plugs and the slab pocket (Figs. 2 and 3). Rapid hardening grout of ordinary strength that flows into gaps without bleeding or segregation is recommended for the LNSC. The height of the plug is 115 mm (i.e., less than the 150-mm height of the slab) to allow for additional cover or waterproof grout.

Fig. 3 shows that a hardened plate washer is used to uniformly distribute the bolt thrust on the upper face of the concrete plug without inducing cracks. The plate washer has a diameter of 90 mm, a central hole with an 18-mm diameter, and a 10-mm thickness. Tightening of Nut 3 (Fig. 3) is performed before hardening of the grout to avoid developing internal stresses in the slab. This way bolt tightening does not result in cracking of the slab due to imperfections in the steel beam-concrete slab interface (Badie and Tadros 2008).

It should be mentioned that different configurations of the LNSC could be adopted by using different numbers of bolts. For example, one bolt in one precast concrete plug within a single slab pocket can be adopted to reduce the quantity of in situ grout or four bolts in a single plug within a single slab pocket could be adopted to increase the total shear strength, reducing the shear connectors needed along the length of the bridge.

256 **Procedure for Accelerated Bridge Assembly**

257 Prefabrication of all structural components can be performed in the
258 shop (i.e., machining of the conical nuts, drilling of the chamfered

holes, positioning of the bolts on the steel beams by fastening the double locking nut configuration, casting of precast concrete plugs, and casting of precast slabs), whereas the final assembly between the precast slab and the steel beam is performed on-site. Each precast concrete panel is positioned on the top of the steel beam so that each pair of bolts is approximately aligned with the center of the slab pocket. Quick-hardening grout is then poured into the slab pocket up to a certain depth. Then, the plugs are placed into the slab pocket so that each plug surrounds a bolt and all gaps are filled with grout. The plugs are then secured in place by tightening Nut 3 in Fig. 3. Hardening of the grout completes the construction process of the LNSC.

270 **Procedure for Accelerated Bridge Disassembly**

271 The LNSC allows rapid disassembly and replacement of any deteriorating
272 structural component of a precast steel-concrete composite bridge.

273 In case of deterioration in a precast concrete panel, the lower
274 nuts (Nut 1 in Fig. 3) are removed and the precast panel along with




Fig. 5. Dimensions of (a) slab pocket and (b) half plug

F5 : 1




Fig. 4. Geometry of the locking connection: (a) full nut; (b) half nut; (c) half countersunk hole

F4 : 1

275 its shear connectors can be rapidly uplifted as a whole. If there is no
 276 access underneath the bridge, the upper nuts at the top of the plugs
 277 (Nut 3 in Fig. 3) are removed and the precast panel can be rapidly
 278 uplifted along with its plugs by leaving the bolts in place. To
 279 achieve that easily, it is important to design the bolts so that their
 280 threaded length is not in contact with the grout.

281 In case of deterioration in a few shear connectors, the plugs
 282 along with their surrounding grout can be rapidly extracted (pulled
 283 out) and replaced, as shown in Fig. 6 [i.e., first the lower nuts (Nut 1
 284 in Fig. 3) are unfastened and then the plugs and their surrounding
 285 grout are removed by applying uplift forces while using the slab as
 286 support]. Optionally, a thin layer of a release agent like a wax-based
 287 material can be applied on the surfaces of the slab pocket before
 288 casting the grout to allow easier removal of the plugs and their sur-
 289 rounding grout.

290 In case of deterioration in the steel beam, the accelerated bridge
 291 disassembly capability allows the beams to be replaced, and the

292 precast concrete panels and shear connectors can be reused. It is
 293 emphasized that robust dry joints among the precast concrete pan-
 294 els, such as those proposed by Hallmark (2012), would further
 295 enhance bridge disassembly.

296 **Experimental Program**

297 **Test Setup and Instrumentation**

298 Push-out tests on the LNSC were conducted using the test setup
 299 shown in Fig. 7. The specimen consists of a pair of slabs connected
 300 to a steel beam by using the LNSC. Both the specimen and the test
 301 setup follow the recommendations of Eurocode 4 (BSI 2004). A hy-
 302 draulic jack with the capacity of 200 tons was used to apply a verti-
 303 cal force on the specimen. Four LVDTs were used to measure slip
 304 between the concrete slabs and the steel beam close to the positions



Fig. 6. Disassembly procedure

F6 : 1




Fig. 7. Setup for push-out tests and instrumentation

F7 : 1

305 of the four bolts. Another pair of LVDTs was used to measure lateral
 306 lateral displacements at the upper tip of the specimen so that any ec-
 307 centricity in the loading could be detected in advance. Moreover,
 308 four LVDTs were used to measure separation (i.e., uplift displacements)
 309 of the concrete slabs from the steel beam close to the positions
 310 of the four bolts. An additional LVDT was used to monitor the jack
 311 displacement and to control the displacement rate during testing.
 312 A load cell with a capacity of 100 tons was used to measure the
 313 applied load directly under the jack. The load is transferred through
 314 a ball joint that ensures that the line of action of the load passes
 315 exactly through the centroid of the steel section without any eccentricity.
 316 This point load is uniformly distributed to the two flanges of the steel
 317 beam with the aid of two spreader beams, which are connected together
 318 by four bolts parallel to the steel section flanges. The internal loads
 319 in the bolts of the LNSC were measured with the aid of washer load
 320 cells with a 200-kN capacity, which were positioned between two plate
 321 washers and then secured by a nut above each concrete plug. The push-
 322 out tests were performed under a load control of 40–60 kN/min during
 323 the initial linear shear load-slip displacement behavior phase, and then
 324 under a displacement control of 0.1–0.2 mm/min during the subsequent
 325 nonlinear shear load-slip displacement behavior phase.
 326

327 **Specimens and Materials Properties**

328 The steel beam has a length equal to 80 cm, a 254 × 254 × 89 UC
 329 section, and S355 steel grade. Four holes with countersunk seat
 330 upper parts [exact dimensions for the case of M16 bolts are shown
 331 in Fig. 4(c)] were drilled on the beam flanges. Four bolts
 332 (threaded at both ends) and four compatible conical nuts [exact
 333 dimensions for the case of M16 bolts are shown in Figs. 4(a and
 334 b)] were fabricated. The bolts along with their conical nuts were
 335 inserted into the countersunk seat holes of the steel beam. Then,
 336 the lower nuts (Nut 1 in Fig. 3) were tightened to the proof load to
 337 securely lock the bolts within the bolt holes. A DTI washer was
 338 used to confirm the proof load limit for each bolt. Fig. 8 shows the
 339 bolts and the conical nuts securely locked within the chamfered
 340 holes of the steel beam.

341 The precast concrete slab had a 650 × 600 × 150-mm geometry
 342 and a central countersunk conical pocket with the exact dimensions
 343 shown in Fig. 5(a). The slab pocket was treated with two layers of a

release agent (Pieri Cire LM-33) from Grace Construction 344
 Products. The slab steel reinforcement was designed according to 345
 Eurocode 4 (BSI 2004). Slabs were cast in horizontal position and 346




Fig. 9. Slab positioned over the steel beam

F9 : 1




Fig. 10. Nut and washer load cell on top of the concrete plugs

F10 : 1



F8 : 1 **Fig. 8.** Bolts and conical nuts securely locked within the chamfered
 F8 : 2 holes of the beam flange

Table 1. Typical Mix Proportions for Slabs, Plugs, and Grout

Material	Slabs (kg/m ³)	Plugs (kg/m ³)	Grout (kg/m ³)
Cement	313	500	910
Cement type	CEM II A-L 32.5 R	CEM I 52.5N	Hanson Quickcem
Water	189	182	455
Sand	825	713	910 fine sand
Gravel	1,093 (size 10 mm)	1,011 (size 10 mm)	—
Superplasticizer	0.8% of cement weight	1.2% of cement weight	—

Table 2. Specifications of Push-Out Tests

Test number	Bolt diameter (mm)	Bolt preloads (kN)		Slabs		Plugs		Grout
		Nuts 1–2 ^a	Nuts 2–3 ^a	Composite strength (MPa)	Tensile strength (MPa)	Composite strength (MPa)	Tensile strength (MPa)	Composite strength (MPa)
1	16	88–106	88–106	31	2.5	65	4.2	122
2	16		0.0					
3	16	88–106	88–106	31	2.5	65	4.2	—
4	16	88–106	10	31	2.5	83	5.2	43
5	16	88–106	88–106	37	—	71	4.3	58
6	16	64	55–70	41	4.0	86	5.1	44
7	12	47–56	24	50	4.0	91	4.8	28
8	14	68–81	23	50	4.0	95	4.6	32
9	16	Failed	23	42	3.6	80	4.8	39
10	16	88–106	24	43	3.1	50	3.7	27
11	16	88–106	26	43	3.2	96	4.8	28
12	16	88–106	26	42	3.5	91	4.9	28

^aSee Fig. 3 for locations of Nuts 1–3.

Table 3. Sieve Analysis of Fine Sand Used in Grouts

Sieve size (mm)	Cumulative (% by weight)	Passing (% by weight)	BSI (1976), Table 1, Type B, passing (% by weight)
0.6	0	100	55–100
0.3	34	66	5–75
0.15	58	8	0–20
0.063	8	0	<5

Table 4. Properties of Bolts

Test	Modulus of elasticity (GPa)	Yield stress (MPa)	Tensile strength (MPa)	Maximum elongation %	Bolt tensile resistance (kN)
Average of nine specimens	209	787	889	8	—
Min.	201	719	832	5	—
Max.	215	847	950	15	—
Standard deviation	5	50	41	5	—
D12 mm	—	—	—	—	100.5
D14 mm	—	—	—	—	136.9
D16 mm	—	—	—	—	178.7

347 then positioned over each flange of the steel beam, as shown in Fig.
 348 9. Grout was poured into the slab pockets, and then a precast plug
 349 [with the exact dimensions shown in Fig. 5(b)] was placed around
 350 each bolt and gradually inserted into the slab pocket to ensure that
 351 all gaps were filled with grout without leaving any voids.

352 A washer load cell was placed between two plate washers on
 353 the top surface of each plug to measure the tension load inside the
 354 bolts, as shown in Fig. 10. Tightening the nut above each plug
 355 (Nut 3 in Fig. 3) completed the fabrication of the LNSC specimen.
 356 All bolts had approximately the same tension force after tight-
 357 ening all nuts above the plugs to ensure symmetrical behavior of the
 358 specimen.

359 Typical mix proportions used to cast concrete slabs, plugs, and
 360 grout are listed in Table 1. Moreover, Table 2 lists specifications for
 361 all push-out tests (discussed in the next section) including concrete
 362 compressive and tensile strengths obtained at the same day of each
 363 push-out test. The maximum size of the gravel was 10 mm. The
 364 sieve analysis (BSI 1976) for the “fine” sand used for the grout is
 365 provided in Table 3. It is important to use such fine sand and not an
 366 ordinary sand to avoid possible segregation of sand particles
 367 between the lower face of the plug and the upper face of the steel
 368 flange. The compressive strengths of the slabs and plugs were evalu-
 369 ated by using standard cubes of a 100-mm length, the compressive
 370 strength of the grout by using cubes of a 75-mm length, and the ten-
 371 sile strengths of the slabs and plugs by using standard cylinders of a
 372 100-mm diameter and 200-mm length.

373 Nine steel coupon specimens, randomly chosen and machined
 374 from bolts, were subjected to tensile tests according to BSI (2009b).
 375 Specimen strains were measured using an axial extensometer.
 376 Average values of the properties of the steel bolts are listed in Table
 377 4, whereas a typical stress-strain relationship from one coupon test
 378 is shown in Fig. 11.

Experimental Results

Preliminary Tests

379 Push-out tests were performed on 12 LNSC specimens with specifi-
 380 cations listed in Table 2. The first six tests were preliminary and
 381 served to investigate how different design details influence the
 382 strength and ductility of the LNSC. The results of these preliminary
 383 tests led to the recommendation of the final robust structural details
 384 of the LNSC. The specimens of Tests 1 and 2 used very high
 385 strength grout, a double nut configuration similar to the work of
 386 Pavlović et al. (2013), and two bolts per plug. These tests showed
 387 early shear failure in the threaded part of the bolts and modest slip
 388 capacity. The specimen of Test 3 used two bolts per plug and a gap
 389 between the bolt and its hole [i.e., similar to the work of Liu et al.
 390 (2014)] with an extra enlargement at the bolt base equal to 20 mm.
 391 Test 3 showed failure due to excessive slip, which was similar to the
 392 failure discussed by Oehlers and Bradford (1999). The specimen of
 393 Test 4 was identical to that of Test 3, but the gap between the bolt
 394 and its hole was filled with a cement-based grout. Test 4 showed
 395 shear failure in the threaded part of the bolt. During the previously
 396 mentioned four tests, a sudden and large slip occurred as a result of
 397 bolts sliding inside the bolt holes when friction resistance in the
 398 steel beam-concrete slab interface was exceeded. To this end, Test 5
 399 aimed to assess the behavior of a nonslip shear connector using a
 400 conical nut connection similar to that of the LNSC but without com-
 401 pletely hiding the threads of the bolt inside the conical nut body, as
 402
 403

shown in Fig. 12 (refer to Fig. 8 for comparison). Finally, Test 6 was conducted on a specimen representing the actual robust structural details of the LNSC. Fig. 13 compares the shear load-slip displacement behavior from Tests 1 to 6 and highlights that the novel structural details of the LNSC result in superior structural performance. In Fig. 13 (as well as in all the shear load-slip displacement curves presented in this paper), the shear load is the applied load divided by four (i.e., number of bolts), whereas the slip displacement is the average of the slip displacements measured close to the four bolts. The ultimate load is the maximum load in the shear load-slip displacement curve, whereas the slip capacity is calculated as the slip displacement corresponding to the ultimate load. It should be noted that Eurocode 4 (BSI 2004) recommended calculating the slip capacity as the one that corresponds to the characteristic load value in the descending branch of the shear load-slip displacement curve. However, to accurately record the descending branch of a push-out test, a very stiff testing rig that does not store high strain energy at the instant of ultimate load (i.e., instant of sudden failure) is required (Johnson 1967).

Confirmation of Results with Identical Tests

Following the recommendation of Eurocode 4 (BSI 2004), the results of Test 6 were confirmed by conducting two additional push-out tests with approximately the same specifications (i.e., Tests 11 and 12 in Table 2). Table 5 lists the ultimate loads and slip capacities from the “identical” Tests 6, 11, and 12. The deviation of the ultimate load of any of the individual tests from the mean value is less than 2%, i.e., significantly below the 10% limit of Eurocode 4 (BSI 2004). Therefore, the characteristic shear resistance may be safely determined as the minimum ultimate load from the three identical tests reduced by 10% according to Eurocode 4 (BSI 2004), i.e., $P_{Rk} = 0.9 \times 189.5 = 170.55$ kN. Fig. 14 compares the shear load-slip displacement behavior from the three identical push-out Tests 6, 11, and 12. The results highlight that the robust structural details of the LNSC result in superior strength, superior stiffness, large slip capacity, and repeatability in the load-slip behavior. Moreover, Suwaed et al. (2016) provided a comparison among the LNSC and previously proposed demountable shear connectors, which shows that the LNSC provides the highest shear resistance.

Comparison with Welded Studs

The shear resistance of the LNSC from Test 6 is equal to 198.1 kN for a slab concrete strength equal to 41 MPa, bolt diameter equal to 16 mm, and bolt tensile strength equal to 889 MPa. According to

442
443
444
445



Fig. 12. Bolts of the shear connector before and after Test 5

F12 : 1




Fig. 11. Typical stress-strain behavior of bolts from tensile coupon tests

F11 : 1




Fig. 13. Comparison of load-slip behavior from Tests 1 to 6

Fig 13 : 1

Table 5. Results of Tests 6, 11, and 12

Test number	Ultimate load (kN)	Slip capacity (mm)
6	198.1	12.2
11	196.7	13.9
12	189.5	13.8
Average	194.8	13.3
Standard deviation	3.76	0.779
Error %	2	6

446 Eurocode 4 (BSI 2004), the shear resistance of welded shear studs
447 is calculated as the minimum of

$$P_R = 0.8 f_u \pi \frac{d^2}{4} \quad (1)$$

and

$$P_R = 0.29 d^2 \sqrt{f_{ck} E_{cm}} \quad (2)$$

448 where d = shank diameter of the welded stud; f_u = ultimate tensile
449 strength of the steel material of the stud; f_{ck} = characteristic compressive
450 cylinder strength of the concrete slab; and E_{cm} = elastic modulus of the concrete. By using the concrete slab strength, stud
451 diameter, and tensile strength of the LNSC from Test 6 in Eqs. (1)
452 and (2), the shear resistance of the corresponding welded shear stud
453 is calculated equal to 73.02 kN from Eq. (2). Therefore, the shear res-
454 istance of the LNSC is significantly higher than that of welded
455 studs. The reason for such higher shear resistance is that the smart
456 structural details of the LNSC promote failure in the shank of a high
457 tensile strength (e.g., 889 MPa) bolt without premature concrete
458 failure, i.e., a behavior that is impossible for welded shear studs of
459 similar high tensile strength. It should be noted that prior research
460 shows negligible effect in the shear resistance of welded shear studs
461 when high-strength grout (e.g., 75 MPa) is used to fill the pockets of
462 the precast slab (Shim et al. 2001). Most importantly, although a
463 tensile strength of 895 MPa was used for the welded shear stud in
464 the previously mentioned calculations, Eurocode 4 did not allow the
465 use of welded studs with tensile strengths higher than 500 MPa
466 (BSI 2004); this is probably because welding steel structural

elements of different steel grades (i.e., shear stud and steel beam) is
not possible.

The slip capacity of the LNSC from Test 6 is equal to 12.2 mm,
i.e., two times higher than the typical 6.0-mm slip capacity of
welded studs. This large slip capacity of the LNSC could be
exploited in the design of long composite beams on the basis of the
partial interaction theory (Johnson and May 1975). The latter
designs cannot be achieved with welded shear studs due to their lim-
ited slip displacement capacity (Johnson 1981).

The LNSC does not show appreciable scatter in its behavior
(Fig. 14) compared with the scatter seen in the behavior of welded
shear studs [e.g., see results in Xue et al. (2008)]. The main reason
for this is that the smooth flowable grout used to cover all gaps
among the elements of the LNSC ensures uniform distribution of
bearing stresses in the conical nut-grout, bolt shank-grout, and
plug-grout interfaces. Such uniform distribution of bearing stresses
cannot be ensured in the area around the collar of welded shear
studs due to the existence of voids and/or the variation in local
arrangement of the aggregate particles (Johnson 2004).

Load-Slip Behavior and Failure Mode

The shear force transfer mechanism of the LNSC initiates with fric-
tion forces in the steel flange-concrete plug interface. The concrete
plugs transfer these forces to the slab through the grout in their inter-
face. When the shear forces exceed the friction resistance in the
steel flange-concrete plug interface, slip occurs. Then, apart from
friction, shear forces are also transferred from the steel flange to the
conical nut and the bolt shank through bearing. The conical nut and
bolt shank transfer forces to their surrounding grouts. Finally, these
forces are transferred to the concrete plugs and then to the slab
through the grout in their interfaces.

It should be noted that concrete is significantly stronger in triax-
ial compression, i.e., stresses can reach values equal to 10 times the
cylinder strength (Johnson 1967). Oehlers and Bradford (1995) esti-
mated that the concrete adjacent to the collar of a welded stud can
withstand 7.0 times its cylinder strength. The part of the concrete
plug in front of the conical nut is under nearly triaxial stress confine-
ment conditions due to the pretensioning of Nut 3 in Fig. 3; there-
fore, it can develop stresses much higher than its 80- to 100-MPa
design strength. Therefore, bolts will always shear off before the




Fig. 14. Behavior of shear connector from three identical push-out tests (6, 11, and 12 in Table 2)




Fig. 15. Results of Test 12 for slip displacement up to 1.0 mm

F14 : 1

F15 : 1

506 concrete plug tails. On the other hand, the existence of ordinary
 507 strength grout enables the bolts to deflect by crushing the grout in
 508 the plug-bolt interface. Such bolt deflection enables the LNSC to
 509 develop its large slip capacity.

510 The shear load-slip displacement behavior of the LNSC (Fig.
 511 14) consists of three regions. The first region covers slip displacements
 512 from 0.0 to 1.0 mm in which the shear load reaches values up
 513 to 100 kN, i.e., approximately equal to 50% of the shear resistance,
 514 which means that the stiffness of the LNSC for the M16 bolt is 100
 515 kN/mm. Similar stiffness can be offered by 19-mm-diameter
 516 welded studs according to Eurocode 4 (BSI 2004), which shows the
 517 superior stiffness of the LNSC. Fig. 15 plots the results of Test 12
 518 for slip displacements up to 1.0 mm and shows that no slip occurs
 519 for shear loads lower than 12 kN. This initial nonslip behavior is
 520 due to friction within the steel flange-concrete plug interface. A

friction resistance equal to 12 kN indicates a value of the friction
 coefficient equal to 0.5 [on the basis of the 26-kN bolt preload in
 Test 12 (Table 2)], which is compatible with the recommendation
 of BS 5400-5 (BSI 1979) for steel-concrete interfaces. Please note
 that bolt preloading is performed before grout hardening; therefore,
 100% of the bolt preload is transferred as normal force in the steel
 flange-concrete plug interface. It should be mentioned that when the
 shear load exceeds the shear resistance, no sudden slip is seen in the
 behavior of the LNSC due to the locking nut configuration. Moreover,
 as the slip displacement increases, the length of the bolts increases
 and their internal forces slightly increase. The latter results in
 gradual increase of the friction resistance.

The second region of Fig. 14 covers slip displacements from 1.0
 to 2.5 mm in which the shear load reaches values up to 130–150 kN,
 i.e., approximately equal to 75% of the shear resistance. In this

521
 522
 523
 524
 525
 526
 527
 528
 529
 530
 531
 532
 533
 534
 535




Fig. 16. Deflected shapes of the bolts from push-out Tests 6, 11, and 12

F16 : 1



Fig. 17. Slab spalling after push-out Test 6

F17 : 1

536 region, gradual yielding of bolts in combined shear and bending
 537 along with crushing of the grout in front of the conical nut and the
 538 bolt shank take place. At the end of this region, the bolts form two
 539 short length regions of high plasticity (i.e., “plastic hinges” due to
 540 combined shear, bending, and axial internal stresses) separated by a
 541 30- to 40-mm straight part.


542 The last region in Fig. 14 covers slip displacements from 2.5 mm
 543 to about 14 to 15 mm, in which the shear load reaches its 180- to
 544 200-kN ultimate value. This region starts with the conical nut and
 545 bolt shank gradually bearing against the concrete plug. The latter
 546 action increases the concrete shear strains in the part of the plug that
 547 is in front of the conical nut. Then a concrete shear failure plane
 548 forms and passes through the grout-plug-grout-slab interfaces, start-
 549 ing just above the conical nut and ending just above the steel flange
 550 (slab spalling). The previously mentioned concrete shear failure
 551 shifts the bearing stresses from the locking nut to the bolt shank and
 552 finally leads to shear failure through an elliptical cross section of the
 553 bolt shank just above the conical nut (Fig. 16). It should be noted
 554 that deformations in the bolts of the LNSC are a combination of
 555 shear, bending, and tensile deformations. Similar behavior was
 556 observed in welded studs in which the combination was 56% bend-
 557 ing deformations and 37% shear deformations (Pavlović et al.

2013). It should be noted that higher tensile deformations in shear
 558 studs could occur at specific locations of a bridge (e.g., close to
 559 transverse bracing) due to large tensile forces (Lin et al. 2014). This
 560 case is explicitly addressed in Eurocode 4 (BSI 2005b), which rec-
 561 ommended the use of additional anchorage mechanisms (e.g., steel
 562 plates welded on the top flange of the steel beam) (Vayas and
 563 Iliopoulos 2014) instead of designing the shear studs to resist such
 564 large tensile loads. Also note that bolts subjected to combined shear
 565 and pretensioning do not necessarily exhibit reduction in their shear
 566 resistance. For example, Pavlović (2013) did not notice any influ-
 567 ence on shear strength for preloading up to 100% of proof load. The
 568 latter also has been highlighted by Wallaert and Fisher (1964), in
 569 which it was explained that when a bolt is torqued to a certain pre-
 570 load, most of the inelastic deformations develop in the threaded por-
 571 tion of the bolt and not in the shank. Therefore, the shear resistance
 572 is not decreased when the failure plane is within the shank. It is
 573 interesting to note that spalling of the concrete slab was minor and
 574 without any global cracking or splitting in the LNSC tests (Fig. 17).
 575 The latter implies that in the case of the LNSC, and contrary to
 576 welded studs, there is no need for additional transverse reinforc-
 577 ment in the slab (BSI 2005b).
 578

Load-Slab Uplift Behavior


579
 580 During a standard push-out test (Oehlers and Bradford 1995), slabs
 581 tend to uplift as they slide over the collar of welded studs (Johnson
 582 2012). Eurocode 4 (BSI 2004) and other researchers (Yam 1981)
 583 recommended that the slab uplift (i.e., slab separation) should be no
 584 more than 50% of the corresponding slip displacement for shear
 585 load equal to 80% of the shear resistance. Fig. 18 shows that slab
 586 separation is less than 0.1 mm at 80% of loading, i.e., only 4% of
 587 the corresponding slip displacement. Push-out tests on welded studs
 588 of the same bolt diameter showed uplift displacements equal to 9–
 589 15% of the corresponding slip displacements (Spremić et al. 2013).

590 Fig. 19 shows that the internal bolt force in the LNSC increases
 591 almost linearly with the slip displacement and finally reaches a
 592 value of 70–75 kN (i.e., 40% of the bolt tensile resistance) at the
 593 onset of failure. The angle of the line of action of this force from the
 594 vertical gradually increases as the slip displacement increases.
 595 Therefore, the internal bolt force has a vertical component that con-
 596 tributes to friction resistance and a horizontal component that
 597 directly contributes to shear resistance.



F18 : 1

Fig. 18. Comparison of slab separation from Tests 6, 11, and 12



F19 : 1

Fig. 19. Bolt internal force from Tests 11 and 12

Table 6. Angle β of the Deflected Shape of the Bolt from the Vertical (in Degrees): M16 bolts of Tests 11 and 12

Test number	Bolt 1	Bolt 2	Bolt 3	Bolt 4	Average
11	12.9	12.1	12.1	9.7	11.7
12	11.3	11.3	13.7	13.7	12.5
Average	12.1	11.7	12.9	11.7	12.1

598 **Design Equation**

599 Eurocode 4 recom^{me}nded that the shear resistance of a connector
 600 failing due to steel fracture can be calculated by using Eq. (1). In the
 601 case of the LNSC, Eq. (1) should be modified to account for
 602 the effect of friction in the steel flange-concrete plug interface,
 603 the effect of the inclination of the deflected shape of the bolts
 604 [similarly to the work of Chen et al. (2014)], and the effect of
 605 shear failure through an elliptical cross section of the bolt shank

$$P = 0.8f_u \left(\frac{\pi d^2}{4 \cos \beta} \right) + T(\sin \beta + \mu \cos \beta) \quad (3)$$

where β = angle of the deflected shape of the bolt from the vertical
 at the level of the shear failure plane; μ = coefficient of friction
 between concrete and steel; and T = tensile force in the bolts at the
 onset of failure. T was found equal to 40% of the bolt tensile resist-
 ance at the onset of failure (Fig. 19); therefore, after substitution
 and rearrangement Eq. (3) becomes

$$P = \frac{\pi d^2 f_u}{4} \left[\frac{0.8}{\cos \beta} + 0.4(\sin \beta + \mu \cos \beta) \right] \quad (4)$$

where for Tests 11 and 12, $f_u = 889$ MPa from Table 4; $d = 16$ mm
 from Table 2; $\mu = 0.5$; and $\beta = 12.1^\circ$ from Fig. 16 and Table 6.
 Substitution of these values in Eq. (4) results in shear resistance
 equal to 196.2 kN, which is equal to the average shear resistance




Fig. 20. Effect of bolt diameter on the load-slip behavior

F20 : 1




Fig. 21. Deflected shapes of D12, D14, and D16 bolts from Tests 7, 8, and 12

F21 : 1

Table 7. Results of Tests 7, 8, and 12

Test number	Bolt diameter (mm)	Collar height (mm)	Conical nut width (mm)	Ultimate load (kN)	Slip capacity (mm)	Ultimate load/bolt tensile resistance ^a	Bolt internal load/bolt tensile resistance ^a
7	12	2.5	23	99.3	7.0	0.99	0.34
8	14	5.0	27	155.2	12.9	1.1	0.35
12	16	6.0	29	189.5	13.8	1.1	0.45
Average	—	—	—	—	—	1.06	0.38
Standard deviation	—	—	—	—	—	0.0596	0.0497
Error %	—	—	—	—	—	6	13

^aBolt tensile resistance is provided in Table 4.

614 from push-out Tests 6, 11, and 12 in Table 5. It is interesting to note
 615 that by substituting $\mu = 0.5$ and $\beta = 12.1^\circ$ into Eq. (4), the shear
 616 resistance of the LNSC becomes equal to 1.1 times the bolt tensile
 617 resistance. The latter value is significantly higher than the pure shear
 618 resistance of a bolt of the same diameter, i.e., 0.58 times the tensile
 619 resistance (BSI 2005a).

Experimental Parametric Studies

620

Effect of Bolt Diameter (Tests 7, 8, and 12)

621

Three bolt diameters, i.e., 12, 14, and 16 mm, were used in push-out
 622 Tests 7, 8, and 12 (Table 2) to explore the validity of Eq. (4). The
 623 shear load-slip displacement curves and the deflected shapes of the
 624

Table 8. Angle β (in Degrees) and Length of Deflected Shape for M12, M14, and M16 Bolts

Bolt diameter (mm)	Bolt 1	Bolt 2	Bolt 3	Bolt 4	Average	Deflected length (mm)
12	7.7	9.9	8.5	9.9	9.0	28
14	10.5	11.3	11.3	12.1	11.3	35
16	11.3	11.3	13.7	13.7	12.5	40




Fig. 22. Effect of bolt diameter on slab uplift displacement

F22 : 1

Table 9. Effect of Plug Concrete Strength on M16 Shear Connector Behavior

Test number	Bolt diameter (mm)	Plug strength (MPa)	Ultimate load (kN)	Slip capacity (mm)	Ultimate load/bolt tensile resistance ^a	β (degrees)
10	16	50	180.7	14.7	1.01	13.0
11	16	96	196.7	13.9	1.10	11.7
12	16	91	189.5	13.8	1.06	12.5

^aBolt tensile resistance is provided in Table 4.

bolts from these tests are shown in Figs. 20 and 21, respectively. Results of these tests are listed in Tables 7 and 8 and show that all connectors have large slip capacity (i.e. larger than the 6-mm limit of Eurocode 4) (BSI 2004). Moreover, the values of the seventh column in Table 7 confirm that the LNSC shear resistance can be approximately obtained as 1.1 times the bolt tensile resistance.

Substituting appropriate values for the M14 bolt into Eq. (4) results in shear resistance equal to 149.2 kN, which is only 4% lower than the corresponding value in Table 7. Similarly, Eq. (4) provides a shear resistance equal to 107.6 kN for the M12 bolt, which is only 8% higher than the corresponding value in Table 7. The earlier results show that Eq. (4) reliably predicts the resistance of the LNSC for three different bolt diameters.

Fig. 22 shows the effect of bolt diameter on slab uplift displacement in which the vertical axis represents the ratio of the applied load to the shear resistance, whereas the horizontal axis represents the ratio of the uplift displacement to the slip capacity. It is interesting to note that no uplift occurs for loads up to 60–70% of the shear resistance. Furthermore, at the onset of failure, the uplift displacements are equal to only 3, 4, and 5% of the corresponding slip displacements for M16, M14, and M12 bolts, respectively.




Fig. 23. Comparison between the predictions of Eq. (4) and the push-out tests results

F23 : 1
F23 : 2




Fig. 24. Effect of plug concrete strength on load-slip behavior (Tests 10, 11, and 12)



Fig. 25. Effect of plug concrete strength on slab spalling

Effect of Plug Concrete Strength (Tests 9–12)

Push-out Tests 10–12 (Table 2) investigated the effect of plug concrete strength (i.e., 50, 91, and 96 MPa) on the LNSC behavior. Test 9 used plugs of 80-MPa concrete strength but failed due to accidental loss of bolt pretension; therefore, its results are not presented. The results of Tests 10–12 are presented in Table 9 and in Figs. 23–27.

Table 9 shows that changing the plug concrete compressive strength from C96 to C50 results in modest changes in the shear resistance (9% decrease) and slip capacity (5% increase) of the LNSC. These results further confirm that, unlike conventional studs, which have several modes of failure (BSI 1994), the LNSC has only one failure mode, i.e., shear failure of bolts just above the locking nuts.

Table 10 and Fig. 23 provide a comparison among the predictions for the shear resistance of the LNSC from Eq. (4) and the corresponding experimental values. It is shown that Eq. (4) provides good estimations with a maximum absolute error less than 8%. Eq. (4) predicts the shear resistance of the LNSC, which was obtained on the basis of standard push-out tests and specimen dimensions according to EC4 (BSI 2005b), for plug concrete strengths between 50 and 100 MPa, bolts with a steel strength of 889 MPa and diameter from 12 to 16 mm, grout compressive strength from 25 to 45 MPa, a full proof load (88–106 kN) between Nuts 1 and 2 (Fig. 4), and an initial internal bolt force equal to 25 kN.

Fig. 24 shows the effect of plug concrete strength on the shear load-slip displacement behavior. The plug concrete strength has no effect for loads up to 32% of the shear resistance, which is similar to

welded studs (Oehlers and Coughlan 1986). An increase of the plug concrete strength from C50 to C96 increases the stiffness from 78 to 106 kN/mm at a shear load equal to 50% of the shear resistance. Fig. 25 shows the bottom face of the slabs after failure of the specimens of push-out Tests 10 and 11. Negligible differences can be noticed between the C50 and C96 plug concrete strength specimens. Moreover, Fig. 25 shows that spalling extends only within a 20-mm circular pattern inside the slabs.

Fig. 26 shows that as the plug concrete strength increases, less slab uplift displacement occurs. A 92% increase in plug concrete strength results in 33% reduction in uplift displacement at the onset of failure. Fig. 26 also highlights that slab separation starts for loads higher than 50% of the shear resistance and has a maximum value that is less than 0.5 mm at the onset of failure. These results further confirm that the LNSC has superior stiffness and strength against slab uplift.

Fig. 27 shows the deflected shape of bolts after failure of the specimens of push-out Tests 10–12. All bolts have similar deflected shapes, which is an observation that further indicates that plug concrete strength has little effect on the LNSC behavior.

Summary and Conclusions

A novel demountable LNSC for precast steel-concrete composite bridges has been presented. The LNSC uses high-strength steel bolts, which are fastened to the top flange of the steel beam using a locking nut configuration that prevents bolts from slipping inside their holes. Moreover, the locking nut configuration resembles in geometry the collar of welded shear studs and prevents local failure within the threaded part of the bolts to achieve higher shear resistance and ductility. The bolts are surrounded by conical precast high-strength concrete plugs, which have dimensions to easily fit within the precast slab pockets. Grout is used to fill all the gaps between the bolts, the precast plugs, and the precast slab pockets, whereas tightening of a nut at the top of the LNSC secures the plugs in place before grout hardening. Six preliminary push-out tests were conducted to fully illustrate why the novel structural details of the LNSC result in superior shear load-slip displacement behavior. Six additional push-out tests served to assess the repeatability in the LNSC behavior as well as to quantify the effects of the bolt diameter and the concrete plug strength. A simple design equation to predict the shear resistance of the LNSC was proposed. Based on the results presented in the paper, the following conclusions are drawn:




Fig. 26. Effect of plug concrete strength on slab uplift displacement (Tests 10, 11, and 12)



Fig. 27. Deflected shapes of M16 bolts for different plug concrete strengths

Table 10. Comparison among the Predictions of Eq. (4) and the Push-Out Tests Results

Test number	Bolt diameter (mm)	Plug strength (MPa)	Ultimate load (kN)	Eq. (4) (kN)	Error %
7	12	91	99.3	107.6	8.0
8	14	95	155.2	149.2	-4.0
10	16	50	180.7	190.7	6.0
11	16	96	196.7	195.5	-1.0
12	16	91	189.5	196.8	4.0

715 1. The LNSC allows rapid bridge disassembly and easy replace- 733
 716 ment of any deteriorating structural component (i.e., precast 734
 717 deck panel, shear connector, steel beam). Therefore, the use of 735
 718 the LNSC in practice can result in significant reduction of the 736
 719 lifecycle direct and indirect socioeconomic costs related to 737
 720 maintenance, repair, or replacement of precast steel-concrete 738
 721 composite bridges. 739
 722 2. The LNSC promotes accelerated bridge construction by taking 740
 723 full advantage of prefabrication. In particular, fabrication 741
 724 of all structural components is performed in the shop and only 742
 725 the final assembly between the precast slab and the steel beam 743
 726 is performed on-site. Moreover, the latter does not involve 744
 727 working underneath the bridge deck. 745
 728 3. The LNSC has very high shear resistance and stiffness, 746
 729 leading to reduction of the required number of shear connec- 747
 730 tors and slab pockets compared with welded studs or 748
 731 previously proposed bolted shear connectors. The charac- 749
 732 teristic shear resistance and stiffness of the LNSC for an 750

M16 bolt were found equal to 170.5 kN and 100 kN/mm, 733
 respectively. 734
 4. The LNSC has very large slip capacity, i.e., up to 14.0 mm. 735
 5. The LNSC has superior stiffness and strength against slab uplift 736
 compared with welded studs, e.g., the uplift displacement is less 737
 than 4% of the corresponding slip displacement at shear load 738
 equal to 80% of the shear resistance. 739
 6. The shear load-slip displacement behavior of the LNSC shows 740
 repeatability and negligible scatter. Among three identical 741
 push-out tests, the maximum deviations of any individual test 742
 from the average were only 2 and 6% for the shear resistance 743
 and slip capacity, respectively. 744
 7. Increasing the plug concrete strength from C50 to C96 was 745
 found to have negligible effect on shear resistance (9% 746
 increase) and slip capacity (5% decrease). 747
 8. The proposed design equation [Eq. (4) in the paper] was 748
 checked against test results of specimens with different bolt 749
 diameters and plug concrete strengths and was found to 750

751 predict the shear resistance of the LNSC with maximum absolute error less than 8%.
 752
 753 9. The shear resistance of the LNSC could be approximately
 754 considered equal to 1.1 times the bolt tensile resistance for
 755 preliminary design purposes.
 756 10. More parametric push-out tests and fatigue tests should be conducted to confirm and extend the knowledge on the LNSC
 757 behavior. Moreover, full-scale precast steel-concrete composite
 758 beam tests are needed to assess the behavior of the LNSC within
 759 boundary conditions similar to those encountered in practice.
 760

761 **Acknowledgments**

762 This work was financially supported by the Iraqi Ministry of
 763 Higher Education and Scientific Research (Ph.D. scholarship to
 764 the first author) and from the University of Warwick through its
 765 Strategic EPSRC Impact Fund (awarded to the second author).
 766 Hanson Cement & Packed Products Ltd. and Grace Construction
 767 Products Ltd. donated raw materials for the fabrication of the test
 768 specimens. Emeritus Professor Roger P. Johnson of the University
 769 of Warwick kindly reviewed interim technical reports and offered
 770 comments and advices of significant value. Dr. Melody Stokes of
 771 Warwick Ventures Ltd. facilitated the process of receiving
 772 constructive feedback from international structural engineering
 773 consulting firms. Technical staff of the University of Warwick
 774 provided valuable help with the experimental setup and program.
 775 The authors gratefully acknowledge the previously mentioned
 776 support. Any opinions, findings, and conclusions expressed in this
 777 paper are those of the authors and do not necessarily reflect the
 778 views of the previously mentioned sponsors and supporters.

779 **References**

780 ASCE. (2014). "Infrastructure report card: A big win for water resources."
 781 ([http://www.infrastructurereportcard.org/a/#p/bridges/conditions-and](http://www.infrastructurereportcard.org/a/#p/bridges/conditions-and-capacity)
 682 [-capacity](http://www.infrastructurereportcard.org/a/#p/bridges/conditions-and-capacity)) (Oct. 23, 2016).
 783 Ataei, A., Bradford, M. A., and Liu, X. (2016). "Experimental study of composite beams having a precast geopolymer concrete slab and deconstructable bolted shear connectors." *Eng. Struct.*, 7, 1–13.
 784
 785 Badie, S. S., and Tadros, M. K. (2008). *Full-depth precast concrete bridge deck panel systems*, Transportation Research Board, Washington, DC.
 786
 787 Ban, H., Uy, B., Pathirana, S. W., Henderson, I., Mirza, O., and Zhu, X. (2015). "Time-dependent behaviour of composite beams with blind bolts under sustained loads." *J. Constr. Steel Res.*, 112(Sep), 196–207.
 788
 789 Biswas, M. (1986). "On modular full depth bridge deck rehabilitation." *J. Transp. Eng.*, 10.1061/(ASCE)0733-947X(1986)112:1(105), 105–120.
 790
 791 BSI (British Standards Institution). (1970). "Specification for wheels for agricultural machinery, implements and trailers. Part 3: Nuts." *BS 3486-3*, London.
 792
 793 BSI (British Standards Institution). (1976). "Specifications for building sands from natural sources." *BS 1199*, London.
 794
 795 BSI (British Standards Institution). (1979). "Steel, concrete and composite bridges. Part 5: Code of practice for design of composite bridges." *BS 5400-5*, London.
 796
 797 BSI (British Standards Institution). (1994). "Draft for development: Eurocode 4: Design of composite steel and concrete structures. Part 1-1: General rules and rules for buildings." *BS EN 1994-1-1*, London.
 798
 799 BSI (British Standards Institution). (2004). "Eurocode 4: Design of composite steel and concrete structures. Part 1-1: General rules and rules for buildings." *BS EN 1994-1-1*, London.
 800
 801 BSI (British Standards Institution). (2005a). "Eurocode 3: Design of steel structures. Part 1-1: General rules and rules for buildings." *BS EN 1994-1-1*, London.
 802
 803
 804
 805
 806
 807
 808
 809

BSI (British Standards Institution). (2005b). "Eurocode 4: Design of composite steel and concrete structures. Part 1-2: General rules and rules for bridges." *BS EN 1994-2*, London. 810
 BSI (British Standards Institution). (2005c). "High-strength structural bolting assemblies for preloading. Part 3: System HR, hexagon bolt and nut assemblies." *BS EN 14399-3*, London. 811
 BSI (British Standards Institution). (2005d). "High-strength structural bolting assemblies for preloading. Plain chamfered washers." *BS EN 14399-6*, London. 812
 BSI (British Standards Institution). (2009a). "High-strength structural bolting assemblies for preloading. Part 9: System HR or HV–direct tension indicators for bolt and nut assemblies." *BS EN 14399-9*, London. 813
 BSI (British Standards Institution). (2009b). "Metallic materials–tensile testing. Part 1: Method of test at ambient temperature." *BS EN ISO 6892-1*, London. 814
 Chen, Y.-T., Zhao, Y., West, J. S., and Walbridge, S. (2014). "Behaviour of steel–precast composite girders with through-bolt shear connectors under static loading." *J. Constr. Steel Res.*, 103(Dec), 168–178. 815
 Dai, X., Lam, D., and Saveri, E. (2015). "Effect of concrete strength and stud collar size to shear capacity of demountable shear connectors." *J. Struct. Eng.*, 10.1061/(ASCE)ST.1943-541X.0001267, 04015025. 816
 Dallam, L. N. (1968). "High strength bolt shear connectors–pushout tests." *ACI J.*, 65(9), 767–769. 817
 Dallam, L. N., and Harpster, J. L. (1968). "Composite beam tests with high-strength bolt shear connectors." *Rep. 68-3*, Dept. of Civil Engineering, Univ. of Missouri, Columbia, MO. 818
 Deng, Y., Phares, B., Dang, H., and Dahlberg, J. (2016). "Impact of concrete deck removal on horizontal shear capacity of shear connections." *J. Bridge Eng.*, 10.1061/(ASCE)BE.1943-5592.0000832, 04015059. 819
 Hallmark, R. (2012). "Prefabricated composite bridges—a study of dry joints." Licentiate thesis, Dept. of Civil, Mining and Natural Resources Engineering, Lulea Univ. of Technology, Lulea, Sweden. 820
 Henderson, I. E. J., Zhu, X. Q., Uy, B., and Mirza, O. (2015a). "Dynamic behaviour of steel-concrete composite beams with different types of shear connectors. Part I: Experimental study." *Eng. Struct.*, 103, 298–307. 821
 Henderson, I. E. J., Zhu, X. Q., Uy, B., and Mirza, O. (2015b). "Dynamic behaviour of steel-concrete composite beams with different types of shear connectors. Part II: Modelling and comparison." *Eng. Struct.*, 103, 308–317. 822
 Johnson, R. P. (1967). *Structural concrete*, McGraw-Hill, Berkshire, U.K., 32. 823
 Johnson, R. P. (1981). "Loss of interaction in short-span composite beams and plates." *J. Constr. Steel Res.*, 1(2), 11. 824
 Johnson, R. P. (2004). *Composite structures of steel and concrete: Vol. 1: Beams, slabs, columns, and frames for buildings*, 3rd Ed., Blackwell Scientific, Oxford, U.K., 32. 825
 Johnson, R. P. (2012). *Designers' guide to Eurocode 4: Design of composite steel and concrete structures*, 2nd Ed., Thomas Telford, London, 213. 826
 Johnson, R. P., and Buckby, R. J. (1986). "Composite structures of steel and concrete: Vol. 2: Bridges." *Collins professional and technical books*, 2nd Ed., London, 63. 827
 Johnson, R. P., and May, I. M. (1975). "Partial-interaction design of composite beams." *Struct. Engineer*, 53(8), 305–311. 828
 Kwon, G., Engelhardt, M., and Klingner, R. (2011). "Experimental behavior of bridge beams retrofitted with postinstalled shear connectors." *J. Bridge Eng.*, 10.1061/(ASCE)BE.1943-5592.0000184, 536–545. 829
 Kwon, G., Engelhardt, M. D., and Klinger, R. E. (2010). "Behavior of post-installed shear connectors under static and fatigue loading." *J. Constr. Steel Res.*, 66(4), 532–541. 830
 Lin, Z., Liu, Y., and He, J. (2014). "Behavior of stud connectors under combined shear and tension loads." *Eng. Struct.*, 81(Dec), 362–376. 831
 Liu, X., Bradford, M., and Lee, M. (2014). "Behavior of high-strength friction-grip bolted shear connectors in sustainable composite beams." *J. Struct. Eng.*, 10.1061/(ASCE)ST.1943-541X.0001090, 04014149. 832
 Marshall, W. T., Nelson, H. M., and Banerjee, H. K. (1971). "An experimental study of the use of high strength friction grip bolts as shear connectors in composite beams." *Struct. Engineer*, 49(4), 175. 833
 Moynihan, M. C., and Allwood, J. M. (2014). "Viability and performance of demountable composite connectors." *J. Constr. Steel Res.*, 99(Aug), 47–56. 834
 835
 836
 837
 838
 839
 840
 841
 842
 843
 844
 845
 846
 847
 848
 849
 850
 851
 852
 853
 854
 855
 856
 857
 858
 859
 860
 861
 862
 863
 864
 865
 866
 867
 868
 869
 870
 871
 872
 873
 874
 875
 876
 877
 878
 879

- 880 Oehlers, D. J. (1980). "Stud shear connectors for composite beams." Ph.D.
881 thesis, School of Engineering, Univ. of Warwick, Coventry, U.K.
- 882 Oehlers, D. J., and Bradford, M. A. (1995). *Composite steel and concrete*
883 *structural members: Fundamental behavior*, Elsevier Science Ltd,
884 Oxford, U.K.
- 885 Oehlers, D. J., and Bradford, M. A. (1999). *Elementary behavior of compos-*
886 *ite steel & concrete structural members*, Butterworth-Heinemann,
887 Oxford, U.K., 84–94.
- 888 Oehlers, D. J., and Coughlan, C. G. (1986). "The shear stiffness of stud
889 shear connections in composite beams." *J. Constr. Steel Res.*, 6(4),
890 273–284.
- 891 PANTURA. (2011). "Needs for maintenance and refurbishment of bridges
892 in urban environments." ([http://www.pantura-project.eu/Downloads/](http://www.pantura-project.eu/Downloads/D5.3.pdf)
7 893 [D5.3.pdf](http://www.pantura-project.eu/Downloads/D5.3.pdf)) (Oct. 23, 2016).
- 894 Pathirana, S. W., Uy, B., Mirza, O., and Zhu, X. (2015). "Strengthening of
895 existing composite steel-concrete beams utilising bolted shear connec-
896 tors and welded studs." *J. Constr. Steel Res.*, 114(Nov), 417–430.
- 897 Pathirana, S. W., Uy, B., Mirza, O., and Zhu, X. (2016). "Flexural behav-
898 iour of composite steel-concrete utilising blind bolt shear connectors."
899 *Eng. Struct.*, 114(May), 181–194.
- 900 Pavlović, M., Marković, Z., Veljković, M., and Budevac, D. (2013).
901 "Bolted shear connectors vs. headed studs behaviour in push-out tests."
902 *J. Constr. Steel Res.*, 88(Sep), 134–149.
- Pavlović, M. S. (2013). "Resistance of bolted shear connectors in prefabri- 903
cated steel-concrete composite decks." Ph.D. thesis, Univ. of Belgrade, 904
Faculty of Civil Engineering, Belgrade, Serbia. 905
- Shim, C.-S., Lee, P.-G., and Chang, S.-P. (2001). "Design of shear connec- 906
tion in composite steel and concrete bridges with precast decks." *J.* 907
Constr. Steel Res., 57(3), 203–219. 908
- Spremić, M., Marković, Z., Veljković, M., and Budjevac, D. (2013). 909
"Push-out experiments of headed shear studs in group arrangements." 910
Adv. Steel Constr., 9(2), 170–191. 911
- Tadros, M. K., and Baishya, M. C. (1998). "Rapid replacement of bridge 912
decks." *NCHRP Rep. 407*, Transportation Research Board, 913
Washington, DC. 914
- Vayas, I., and Iliopoulos, A. (2014). *Design of steel-concrete composite* 915
bridges to Eurocodes, CRC Press/Taylor & Francis Group, Boca Raton, 916
FL, 490. 917
- Wallaert, J. J., and Fisher, J. W., (1964). "Shear strength of high-strength 918
bolts." Paper 1822, Fritz Laboratory Reports, Lehigh Univ., Bethlehem, 919
PA. 920
- Xue, W., Ding, M., Wang, H., and Luo, Z. (2008). "Static behavior and theo- 921
retical model of stud shear connectors." *J. Bridge Eng.*, 10.1061 922
/(ASCE)1084-0702(2008)13:6(623), 623–626. 923
- Yam, L. C. P. (1981). *Design of composite steel-concrete structures*, Surrey 924
University Press, London, 75. 925

AUTHOR QUERY FORM

AQ1: ASCE Open Access: Authors may choose to publish their papers through ASCE Open Access, making the paper freely available to all readers via the ASCE Library website. ASCE Open Access papers will be published under the Creative Commons-Attribution Only (CC-BY) License. The fee for this service is \$1750, and must be paid prior to publication. If you indicate Yes, you will receive a follow-up message with payment instructions. If you indicate No, your paper will be published in the typical subscribed-access section of the Journal.

AQ2: Please provide the ASCE Membership Grades for the authors who are members.

AQ3: First affiliation: Please add a city for the Univ. of Warwick affiliation.

AQ4: Please provide details of the citation [Suwaed et al. (2016)] in the reference list.

AQ5: Please add a manufacturer's address (city and state) for Grace Construction Products.

AQ6: ASCE (2014) reference: Please confirm the changes made in the URL title.

AQ7: Pantura (2011): please provide a URL that takes the reader directly to the document being cited.

PROOF ONLY